# Observations during MD of June 2<sup>nd</sup> to June 3<sup>rd</sup>, 2010 and Future Plans for SPS Kickers

M.J. Barnes


TE/ABT/FPS

# **SPS Kicker Summary**

System  MKE4	Maximum Temperature (°C) [MD of June 2-3, 2010] 70+	Maximum Pressure (mbar) [MD of June 2-3, 2010]  9.1x10 <sup>-8</sup>	Comments
MKE4	70+	9.1x10 <sup>-8</sup>	
			MD of June 2-3 stopped three times to permit cool-down of MKE4s.  No serigraphed magnets.  Transition pieces installed.
MKE6	~37	9x10 <sup>-7</sup>	Very high out-gassing: Ion pump VPIB_61635 went to "Not valid state" after MD of June 2-3. All 3 magnets serigraphed. Transition pieces installed.
МКР	~35	1.8x10 <sup>-7</sup>	Significant out-gassing of the TIDVG, especially between 21:30hrs and 23:00hrs on June 2.  VGPIB_11902 not working??  Transition pieces installed for 3 S-type modules.
MKDH1/2/3	No PT100	1.2x10 <sup>-7</sup>	Laminated steel. No transition pieces.
MKDV1/2	~31 (MKDV1 & 2)	1.1x10 <sup>-7</sup>	Transition pieces on MKDV1 only.
MKQH	No PT100	1x10 <sup>-7</sup>	Metallic stripes on ceramic. No transition pieces.
MKQV	No PT100	2.5x10 <sup>-7</sup>	No transition pieces.


June 24, 2010 Barnes: SPSU SG 2

### MKE4 & MKE6: Temperature & Vacuum of Worst Magnet




June 24, 2010 Barnes: SPSU SG 3

## MKE6: Vacuum






- > Magnets appear to condition during MD;
- Lowest pressure rise associated with kicker installed for longest period (61631). Not able to determine if "61631" outgassing has reduced with time (61634 was previously 4E2 ferrite, with high out-gassing rate);
- ➤ Ion pump VPIB\_61635 went to "Not valid state" after this MD - maybe caused by high out-gassing?. To be investigated, by vacuum group, during short technical stop (today). Hot off the press: pump now OK.



4

June 24, 2010 Barnes: SPSU SG

## MKP: Vacuum



Pump (VPCIB\_11902) close to TIDVG (11892) in "Not Valid" state, and has been for some time (not interlocked?): needs investigating.

#### Plans & Ongoing Issues/Work

- **►MKE4:** Shorten period of installation of 5 serigraphed MKE4 kicker magnets, from 3 to 2 shutdowns:
  - o During 1st shutdown (end 2010, start 2011) replace one S-type & one L-type magnet;
    - spares of one S-type & one L-type (serigraphed) to be prepared in advance for exchange (1 S-type done);
  - During 2nd shutdown replace one S-type & two L-type magnets (~2 to 3 months reqd.);
    - spares of one S-type & one L-type (serigraphed) to be prepared in advance for exchange;
    - L-type <u>ferrite</u> prepared ready to exchange once L-type kicker is removed from machine (requires significant manpower (1 person year) and 100kCHF investment in hardware, e.g. to help automate pulse conditioning of 3rd magnet).

#### >MKE6

- o Ion pump in VPIB\_61635 now OK (as of 24/06/2010);
  - *Measure SEY for silver paint and ferrite (Mauro);*
  - Measure out-gassing of silver paint when it is warmed up slightly;
  - Transverse impedance to be measured, in clean room, for non-serigraphed and serigraphed magnet (for 2nd spare magnet being prepared).

#### >MKP

- o Pump VPCIB\_11902 (close to TIDVG and MKP1) MAY need replacing. Vacuum group has been asked to check pump at earliest opportunity [out-gassing from TIDVG is NOT good for MKPs!];
  - Longitudinal and transverse impedances currently being measured in clean room.

June 24, 2010 Barnes: SPSU SG 5